

**ADDENDUM #3 for
Navajo Division of Transportation and Navajo Parks & Recreation
Bid Number: 18-01-1768LE**


Little Colorado River Tribal Park: Turning Lanes, Access Road, & Parking Lot – Borrow, Culvert Extensions, Subgrade Preparation, Asphaltic Concrete, Chip Seal, curb and gutter, sidewalks, fence, signing, and striping.

Addendum#3 is issued to clarify questions regarding the Special Provisions from the Arizona Department of Transportation, Standard Specifications for Road and Bridge Construction, 2008 Edition.

Questions:

1. *Can you verify the pounds for the box culvert? The Engineer calls out to use ADOT SD6.01-5 Table 5 (using standard weight of 241.9 lbs/LF), but the total will be over 4,000 lbs not the 3,300 lbs as called out on the plans.* Ans. Your suspicion is correct. If Table V is used for the fill, then then steel quantity would be 4,284 pounds, as the inquiry suggests. Since Table I fill should actually be used, the 3,344 pounds shown on the plans is correct.
2. *I have a question regarding bid item 6018101, the Reinforced Concrete Box Culvert (10'x5'). From the drawings, sheet 4 of 30 provides a table with dimensions and quantities for the box culvert. It shows the box culvert will be extended a total length of 17ft, it will have inlet/outlet wings, and an apron. My question is the existing structure has wings and a headwall, the wings (both inlet and outlet) will be extended only? Not the headwall? Please clarify.* Ans. The existing headwall and wings shall be removed and the barrel extended as shown on the Table; the new wings and headwalls built on the new barrel ends inlet and outlet; and apron for outlet end.
3. *My question. Item No. 2020037 Remove and Salvage Cattle Guards. In the Special Provisions, "Page 44 of 154, ITEM 2020037 – REMOVE & SALVAGE CATTLE GUARDS: Construction Requirements: The Salvaged grate shall be delivered to the Superior Maintenance Yard located at 951 Main Street, Superior, Arizona 85273. All other materials shall be property of the contractor." In the Plans for Project Little Colorado River Tribal Park, Sheet 10 of 30, "Exst Cattle Guard: Remove, Salvage & Deliver to Gray Mountain Maintenance Yard." What is the owner's decision on the salvage location – Superior, Arizona or Gray Mountain Maintenance Yard?* Ans. The note regarding REMOVING & SALVAGING CATTLEGUARDS is removed i.e. the CATTLEGUARDS become the property of the Contractor.

END OF ADDENDUM #3



Don Jackson, Engineer
Navajo DOT, Dept of Roads
Email: djackson@navajodot.org

Information source: Bob Hansman, P.E., Dibble Engineering.